

Seal:

Revision:

NO.	DATE	BY	DESCRIPTION

Keyplan:

THOMAS RESIDENCE
MASTER PLAN
FLORISSANT, MISSOURI

Scale:

Project No.: 001124

Drawing Title:

LANDSCAPE PLAN AND NOTES

Designed By:
Drawn By:
Checked By:

Drawing No.
L02

See notes below for existing plants to be removed. Plants that are removed under this contract should be removed completely including grubbing and hauled from site. After removal, till in two equal parts of commercially available compost and coarse sand. Beds in the areas to be built in the first phase should be finished with 2 inch layer of river gravel mulch.

- 1 Red lava rock to remain for phase one work. Replace with river gravel for phase 2 work.
- 2 Remove brick edging at end of bed only and stockpile per owner direction.
- 3 Remove, grub and haul the Yews, Arborvita and Hydrangea in their entirety prior to placing new plants in phase 1.
- 4 Hand dig as needed around existing Oak (phase 3).
- 5 Natural limestone units of varying sizes, consistent coloration, 2 units high to include 1st buried coarse. Approximate sizes as follows:
lengths: 6 to 12 inches
width: 8 inches
height: 4 inches
- 6 Trench bed edge
- 7 Mexican beach pebbles on filter fabric (phase 1)

